

Terms and conditions of delivery and installation

Delivery and accessibility

The unloading and installation location must be accessible with a truck and van by a paved road. The workspace, doorway and sliding space must be free of obstacles and building materials.

All delivered goods must be stored covered. Salco can't be held liable for damage caused on site by e.g. exposure to sunlight and rain.

Installation in general

The required architectural recesses for the doors must be provided by the client in advanced. This must be carried out accordingly, accurately and perpendicular to the installation drawings provided by Salco.

For electrical tools, a stable 230V power supply must be available within 25m of the workspace during installation.

For a good seal of the door, the floor must be hardened, flat and level.

The floor must be accessible with a scissor lift up to 2,000 kg. For doors to be mounted on the outside wall, the outside area must also be flat, hardened and accessible with a scissor lift on solid wheels.

The position of the control box, pull switch, radar and the adjustment of the sensors is always determined in consultation with the client. If a customer specific drawing has been made, this is used as a guideline.

Unless stated otherwise, the pricing is based on continuous assembly, adjustment of the door and configuration of the control box. Salco is not responsible for the disposal of disassembled doors, packaging materials and any replaced products.

The client must provide accomodation for a lunch break and sanitary facilities.

Installation in detail

Before installation of the threshold and the pouring of the concrete, the floor level must be clearly marked on the wall next to the clear opening by the customer. It is not possible to install the threshold without a floor level marking.

Airlock, ATU and ATL doors must be installed before the roller conveyor is installed. Once the roller conveyor has been installed, the prescribed safety requirements and calculated installation time can't be met. The extra safety provisions and installation hours will be charged to the client.

When installing high-speed doors and fire resistant curtains, the client must make a forklift available on site for placing the top roller.

Electricity

For electrically operated doors, the definitive power supply (400V or 230V) must be present, functional and installed according to the drawing. If not, Salco is forced to configurate the door after the definitive power supply has been installed. The additional travel and labor costs incurred will be charged to the customer.

The heating of the door, door frame, rail and threshold must be connected by the customer after commissioning, if the ambient temperature is below 0° Celsius. This prevents overheating.

fire resistant curtains that are controlled by a fire alarm system must be connected directly after installation. Without this connection, the fire resistant curtains closes automatically.

Colour

Colour deviations may occur with combination orders or accessories supplied in colour by applying different surfaces and/or type of lacquer/coating.

Commisioning

After installation, the door is presented for approval to the customer. If approved, the customer provides the order with any comments and a signature.